

Your Logo
Here

Materials By Location

Your Job Name Here

Masonry

03 - 1st Level Masonry

Name	Description	Qty	Units
#5 Rebar 1' x 8' Pre-Bent	Vertical Drop Bars	37	EA
#5 Rebar x 20'	Bond Beam Horizontal	19	EA
#5 Rebar x 20'	Lintel Horizontal	1	EA
3000 PSI Grout	Bond Beam Grout	4	CU YD
3000 PSI Grout	CMU Cells Grout	6	CU YD
3000 PSI Grout	Lintel Grout	1	CU YD
4" x 8" x 16" Regular Half High Block	Half High Block	107	EA
8" x 8" x 16" Regular Block	Wall Block	1045	EA
8" x 8" x 16" Regular Open Lintel Block	Bond Beam Block	214	EA
8" x 8" x 8" Regular Block	At Openings	38	EA
9 Ga. Galvanized Ladder Wire	Horizontal Reinforcing	1025	FT
Lintel Screen	Bond Beam	284	FT
Mortar Sand	Per CU YD	3	CU YD
Type S Mortar 80# Bags	Block Mortar	18	Bag(s)

15 - Exterior Stone

Name	Description	Qty	Units
16 Ga. 7/8" x 7" Galv. Wall Ties	Wall Ties	321	EA
27 in x 8 ft Metal Lath	Wall Ties	7	EA
Brown Rocked 5-1/2" W x 3-1/8" H Sills	Stone Sill	33	SQ FT
Cultured LedgeStone Brown	Stone Veneer	107	SQ FT

Masonry**15 - Exterior Stone**

Name	Description	Qty	Units
Masonry Cement 80# Bags	Stone Mortar	3	Bag(s)
Mortar Sand	Stone Mortar Sand	1	CU YD

16 - Exterior Brick

Name	Description	Qty	Units
1/2 x 4" Lag Screws	Steel Lintel Fastners	5	EA
16 Ga. 7/8" x 7" Galv. Wall Ties	Wall Ties	156	EA
7/8" Weep Screed x 10'	Brick Flashing	2	EA
Modular 3-1/2 x 2-3/4 x 7-5/8 Brown Brick	Wall Brick	364	EA
Mortar Net	Brick Flashing	16	FT
Mortar Sand	Mortar Sand	1	CU YD
Type S Mortar 80# Bags	Brick Mortar	5	Bag(s)