

Your Logo
Here

Consolidated Materials

Your Job Name Here

Masonry	Name	Qty	Units
	#5 Rebar 1' x 8' Pre-Bent	37	EA
	#5 Rebar x 20'	19	EA
	1/2 x 4" Lag Screws	5	EA
	16 Ga. 7/8" x 7" Galv. Wall Ties	477	EA
	27 in x 8 ft Metal Lath	7	EA
	3000 PSI Grout	10	CU YD
	4" x 8" x 16" Regular Half High Block	107	EA
	7 5/8" Precast Sill x 4 ft 0 in	1	EA
	7 5/8" Precast Sill x 6 ft 2 in	1	EA
	7/8" Weep Screed x 10'	2	EA
	8" Precast Recessed U Lintel 3/0 Door x 4 ft 8 in	1	EA
	8" Precast U Lintel x 5 ft 4 in	1	EA
	8" Precast U Lintel x 7 ft 6 in	1	EA
	8" x 8" x 12" Block	60	EA
	8" x 8" x 16" Regular Block	1045	EA
	8" x 8" x 16" Regular Open Lintel Block	214	EA
	8" x 8" x 8" Regular Block	38	EA
	9 Ga. Galvanized Ladder Wire	1025	FT
	Brown Rocked 5-1/2" W x 3-1/8" H Sills	33	SQ FT
	Cultured Ledgestone Brown	107	SQ FT
	L3x3x1/4 x 4 ft 6 in	2	EA
	Lintel Screen	284	FT
	Masonry Cement 80# Bags	3	Bag(s)
	Modular 3-1/2 x 2-3/4 x 7-5/8 Brown Brick	364	EA
	Mortar Net	16	FT

Masonry	Name	Qty	Units
	Mortar Sand	4	CU YD
	Type S Mortar 80# Bags	22	Bag(s)